BRUHAT BANGALORE MAHANAGARA PALIKE

Name of Work :IMPROVEMENT OF CC ROADS, DRAINS AND OTHER WORKS AT GOWDIKE HOOLA (JODIDHAR NARASIMHAIAH LAYOUT) IN WARD NO 11

EST COST-100.00 LAKHS

Scheduler -B

JOB CODE NO 014-20-000112

Sl No	Particulars of item	Unit	Qty	Sanctioned Rate in Figures	Rate in Words
1	KSRRB M200-21 Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.03 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications, MORTH Specification No. 202 complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	261.33	952.91	
2	KSRRB M200-15.2 Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. iii) Dismantling Stone Masonry.B. Rubble stone masonry in cement mortar. MORTH Specification No. 202 complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	268.62	372.06	
3	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m. excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	1004.235	137.8	
4	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs. with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregtes @ 0.56cum. machine mixed. concrete laid in layers not exceeding 15 cms. thick. well compacted. in foundation. plinth and cills. ncluding cost of all materials. labour. HOM of machinery. curing complete as per specifications. Specification No. KBS 4.1. 4.2 complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	104.835	5714.99	
5	Providing and laying palin / reinforced cement concrete for side drain using M20 nominal mix connerete with OPC cement @ 300kgs. with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.43cum. with super plasticisers @ 3 liters confirming to is 9103-1999 reafirmed-2008 at machine mixed. well compacted for walls and bottom including centering.shuttering. cost of materials.HOM of machinery. curing etc complete excluding cost of steel as per MORTH Specification No. 1500.1700.2200 including cost of materials. labour. HOM complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	212.67	7189.45	

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Basarahalli Division, Bangalore-560057

Scanned by CamScanner

Sl No	Particulars of item	Unit	Qty	Sanctioned Rate in Figures	Rate in Words
6	KSRRB M2200- TMT/MS Bar Reinforcement KSRRB M2200 6 Supplying, fitting and placing TMT bar reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200 - TMT Bars Fe 500 complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Tonne	15.20591	72326.98	
7	Providing & fixing Precast RCC slab of 100mm thick for drain in cement concrete 1:1:5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortar including from work lift charges, curing and concrete finished surface on both side etc.	Sqm	509.94	1615	
8	Removing and resetting of footpath slab complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Sqm	190.2	208.82	
9	KSRB 15.2.2 Providing ruled pointing to stone slab pavements with cement mortar 1:3, 20mm deep, after raking joints , including cost of materials, labour, curing complete as per specifications.	Sqm	99	48.76	
10	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications .KBS	Sqm	91.2	950.82	
11	KSRRB M600-1. Construction of dry lean cement concrete mix CC1:5:10 with OPC cement @160Kgs. with 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum Sub- base over a prepared sub-grade with (coarse and fine aggregate conforming to IS: 383) aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1. cement content not to be less than 160 kg/ cum. optimum moisture content to be determined during trial length construction. concrete strength not to be less than 10 Mpa at 7 days. mixed in a batching plant. transported to site. laid with a paver with electronic sensor. compacting with 8-10 tonnes vibratory roller. finishing and curing complete as per specifications. MORTH Specification No. 601-do- with OPC at 150 kg/cum and coarse aggregate 0.86cum. fineaggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver.complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	313.485	3948.5	

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISON
BENGALURU-560 010

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057

Scanned by CamScanner

	Particulars of item	Unit	Qty	Sanctioned Rate in Figures	Rate in Words
12	KSRRB M100- Wet Mix Macadam KSRRB M100-17 Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No 406 complete as per specification with all lead and lift and as per the directions of the Engineer incharge	Cum	113.485	2001.28	
13	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @	Cum	313.485	5274.56	
14	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and dise etc.. with all lead and lift, complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Sqm	2089.9	72.08	
15	KSRRB M100-4.1. Cost of Haulage Excluding Loading and Unloading MORTH -100/ Chapter 1 Case-1 : Surface Road ITEM no. 17.4 . KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH -100/ Chapter complete as per specification with all lead and lift and as per the directions of the Engineer incharge.	Cum	1534.185	157.092	

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Pasarahalli Division
B.B.M.P.

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Pasarahalli Division, Bangalore-560 ::7

Scanned by CamScanner